

BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineer
Byatarayanapura Division
B.B.M.P., Bangalore - 92


SCHEDULE-B

Issued to :

Original / Duplicate

Name of the Work : Improvements and Ashalting to Canara bank layout roads in ward No. 09 in Vidyaranyapura sub Division.

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	588.33	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	90.72	Rupees Ninety and Seventy Two Paise Only
2	1107.00	Removing B.S. Slab Drain and stacking etc complete as per specifications and directions of engineer in charge of the work	Sqm	50.11	Rupees Fifty and Eleven Paise Only
3	1107.00	Refixing stone slabs of drains and pointing in CM (1:3) etc complete as per specifications and directions of engineer in charge of the work	Sqm	70.04	Rupees Seventy and Four Paise Only
4	3712.50	Scarifying stone metal crust 50mm to 100mm thick with pick axes along with premix carpet/surface dressing and stacking of old serviceable materials within a lead of 100 meters by manual means including cost of all labour charges etc complete as per specifications and directions of engineer in charge of the work	Sqm	72.79	Rupees Seventy Two and Seventy Nine Paise Only
5	556.88	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1121.04	Rupees One Thousand One Hundred Twenty One and Four Paise Only
6	3712.50	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	10.53	Rupees Ten and Fifty Three Paise Only
7	3712.50	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	142.07	Rupees One Hundred Forty Two and Seven Paise Only


Executive Engineer
Byatarayanapura Division
Yelahanka Zone, B.B.M.P.
Bangalore - 560 092

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
8	92.81	Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications. With 80/100 grade bitumen , etc complete as per specifications and directions of engineer in charge of the work	Cum	9981.36	Rupees Nine Thousand Nine Hundred Eighty One and Thirty Six Paise Only
9	131.00	Road marking with hot applied thermoplastic compound with reflect rising glass beads on bituminous surface-providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface to level, uniform and free from streaks and holes etc complete as per specifications and directions of engineer in charge of the work	Sqm	471.96	Rupees Four Hundred Seventy One and Ninety Six Paise Only
10	588.33	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	72.71	Rupees Seventy Two and Seventy One Paise Only


Signature of the Contractor
Assistant Executive Engineer
Byatarayanapura Sub-division
KRIDL BBMP, Bangalore


Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92